KOLAR DISTRIT.

Notification dated 24th August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up 2 P.M., on 27th September 1930, for restoring Kitchayagarpalli Kitchayabatlukunte, Regd. No. 557 of Srinivaspur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 190 (one hundred and ninety only) in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kitchayagarpalli Kitchaiyabatlukunte, Srinivaspur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderers must quote specific rates for all items both in words and in figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for the probable cost of restoring Kitchayagarpalli Kitchayabatlukunte Regd. No. 557 of Srinivaspur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		
1	Earthwork to bund, lead and lift, watering and tamping, etc., complete.	C.yd.		2,006	
1a	Earthwork to trench filling watering and tamping, etc., complete.	,,		371	
2	Corewall in breach between C. S. 8 and 10.	...		...	
a	Excavation for corewall in chittu soil ...	,,		8	
b	Burnt brick in surki mortar for corewall ...	C.ft.		512	
c	Plastering do do ...	Sqr.		5·08	
3	Puddle wall	...		...	
a	C. S. 6 and 8 and C. S. 7 and 8 below ground level in hard soil.	C.yd.		21	
	Puddle wall	,,		67	
4	New stone revetment	,,		642	
5	Turfing	S.yd.		2,285	
6	Grade stones	Each		13	
7	Index stones	,,		13	
8	Register number stone ...	,,		1	
9	Gauge stone	,,		1	
10	Bench mark stones	,,		2	
11	Clearing the bund by removing jungle grade.	,,		10	
12	Removing top soil and Ant hills ...	,,		10	
	Total ...	...	...	...	

No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice.		Rs. a. p.		
1	Earthwork for excavation [illegible]	C.yd.		47	
2	Refilling with consolidation [illegible] excavation	"		47	
3	Sukki mortar concrete	C.ft.		392	
4	Burnt brick in [illegible]	"		356	
5	Burnt stone slab [illegible]	S.ft.		239	
6	Plastering with [illegible]	Sqr.		5·49	
7	Providing wooden plug with [illegible] with locking arrangements	Each		1	
8	Unforeseen items	Lump		sum	
	Total		..	...	
	Waste Weir.				
1	Earthwork excavating foundation ...	C.yd.		48	
2	Concrete with sukki mortar	C.ft.		187	
3	Hand brick [illegible]	"		527	
4	Burnt stone slab [illegible] brick ...	S.ft.		477	
5	Plastering with [illegible] ...	Sqr.		6·78	
6	New stone work ...	C.yd.		89	
7	Draft and approach clearing ...	Lump		sum	
8	Providing joggle joints ...	Each		16	
	Total ...		..	..	
	Contingencies ...		...	...	
	Grand Total		...	...	

Dated 25th August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 26th September 1930, for restoring Byrandapalli-Gonikere Reg. No. Nil, Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 15[illegible] (one hundred and fifty only) in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Byrandapalli-Gonikere Reg. No. Nil, Bowringpet Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of any tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderer must quote separate rates for all items both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for restoring Byrandahalli-Gonikere (Reg. No. Nil, Serial No. 535), Bowringpet Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork to bund watering and tamping R. L. 55·00.	C.yd.		5,028	
	Turfing to bund	Sq.yd.		3,417	
	Removing and resetting old stone work with jelly.	C.yd.		238	
	Setting new stone work with jelly ...	,,		503	
	Providing and fixing grade stone with figuring and painting, etc.	Grades		12	
	Index stones	,,		12	
	B. M. stones	,,		2	
	Registered number stone	,,		1	
	Gauge stone	,,		1	
	Removing and cutting jungle and ant hills in 6 grades only.	,,		6	
	Earthwork excavating for courwall in hard chittu.	C.yd.		30	
	Concrete for foundation for courwall ...	C.ft.		135	
	Burnt brick in surki mortar do ...	,,		900	
	Plastering with surki mortar	Sqrs.		6·67	
	Total to bund ...	...	...	,,	...
	Sluice R. L. 45·00.				
1	Earthwork excavating for cut open the Bund to R. L. 45·00.	C.yd.		19	
	Refilling the some portion with watering and tamping.	,,		20	
	Surki concrete for foundation	C.ft.		321	
	Burnt brick in surki mortar	,,		160	
	Burnt stone slabs 4″ to 6″ thick	Sq.ft.		171	
	Plastering with surki mortar	Sqr.		2·29	
	Providing wooden plug with rod locking arrangements.	L. S.			
	Cutting holes in orifice and cross slopes ...	No.		2	
	Total to sluice ...	...	...	...	...
	Waste Weir R. L. 50·00.				
	Earthwork excavation	C.yd.		37	
	Concrete for foundation	C.ft.		66	
	Burnt brick in surki mortar	,,		303	
	Burnt stone slabs 4″ to 6″ thick	S.ft.		155	
	Plastering with surki mortar	Sqrs.		4·90	
	Rough stone for apron	C.yd.		33	
	Total to weir ...	...	...	...	...
	Grand Total Rupees ...	...	...	...	..

Notice dated 25th August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 27th September 1930, for restoring Hulkur Dodkere (Oorumundinakere), R. No. 211 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompained by a deposit of Rupees 200 (two hundred only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Hulkur Dodkere (Oorumundinakere), Bowringpet Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the agreement bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of the tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderer must express his rates for all items both in words and figures.

10. The tenderer must state the work would be executed at a certain percentage in excess or lower than the estimated rates will be accepted.

Abstract estimate for restoring Tank Doddakere (Oorumundinakere) Registered No. 211 of Bowringpet Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. Bund.		Rs. a. p.		
1	Earthwork with lead and lift, watering and tamping, etc., complete.	Cft.		4,21°	
2	Turfing	Sq. yd.		3,892	
3	Rough stone work new	Cft.		665	
4	Do do ...	"		200	
5	Providing grade and index stones including cutting figures and painting, etc., complete.	Each		14	
6	B. M. stones do ...	"		2	
7	Do Reg. No. stone do ...	"		1	
8	Do gauge stone do ...	"		1	
9	Jungle clearing	"		14	
	II. Shirce at R. L. 42·50.				
1	Constructing front and rear cisterns as per type design.	Lump.		...	
2	Constructing masonry tunnel	Cft.		28	
	III. Existing Right Waste Weir at 50'00.				
1	Burnt brick in surki mortar to raise the body wall from R. L. 50'00 to 51'00.	"		55	
2	Removing and resetting old burnt stone slabs over the body wall.	Sft.		55	
3	Removing and rebuilding apron with new jelly	Cft.		53	
4	Plastering the body wall with surki mortar	Sft.		...	
	Proposed Left Waste Weir 93 ft. in length at R. L. 51'00.				
1	Earth work excavation	Cft.		128	
2	Burnt brick in surki mortar	"		789	
3	Burnt stone slabs ...	"		246	
4	Plastering with surki mortar ...	Sq.		13·04	
5	Rough stone apron	Cft.		92	
6	Providing joggles to stone slabs ...	Each		·33	
	Total ...	...	...	...	...
	Contingencies ...	...	...	...	...
	Grand Total ...	...	...	...	...

1035

Notice dated 25th August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division upto 2 P.M., on 27th September 1930 for Restoring Manjali Tank, R. No. 672 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 450 (four hundred and fifty only) in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Manjali Tank, R. No. 672, Kolar Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries, regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderers must quote specific rates for all items both in words and in figures.

10. The tender stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for Restoring Manjali Tank Registered No. 672 Serial No. 310 of Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	1 Bund.		Rs. a. p.		Rs.
1	Earth work to bund with watering, tamping (including rooting out ant-hills and trees) and lead and left, etc., complete.	C.yd.		4,020	
2	Turfing to bund	S.yd.		7,240	
3	Removing and resetting old stone revetment with new jelly.	C.yd.		1,026	
4	New stone work	"		1,369	
5	Gravel including lead and lift	"		648	
6	Removing and refixing B. M. stones with painting, etc.	No.		2	
7	New grade stones	"		30	
8	Do Index stones	"		30	
9	Gauge stone	"		1	
10	Rooting out trees and ant-hills and prickly pears, etc.	Grade		15	
11	Cutting trenches and scraping over the bund for the combination of new earth work.	"		25	
12	Land Compensation	Acre		0·25	
	Total to Bund ...	...	...	...	...

No.	Items of work	Unit	Rate	Quantity	Cost
	II Sluices.				
	Sluice No. 1				
	Examining and repairing the existing Sluice No. 1	Lump sum			
	Sluice No. 2.				
1	Dismantling the existing sluice No. 2 at C. S. No. 10 and making use of the available materials.	Lump sum			
2	Earthwork cut opening the bund and refilling with watering and tamping, etc.	C.yd.		134	
3	Concrete in Surki mortar	C.ft.		258	
4	Burnt brick in surki mortar	„		[illegible]	
5	B. stone slabs of 6" thick	S.ft.		[illegible]	
6	Plastering with [illegible] ..	Squ.		[illegible]	
7	New stone [illegible] ...	C.yd.		6	
8	Providing [illegible]	Lump sum			
9	Drilling hole [illegible]	Lump sum			
	Cut.	..	...	...	...
	III Weir.				
1	Dismantling the existing m[illegible] Rt. end of bund and clearing [illegible]	L. S		...	
2	Removing apron	Cyd.		87	
3	Earthwork excavating foundation	„		1,766	
a	Conveying the excavated earth to bund [illegible] ing lead and lift.	„		1,590	
4	Filling foundation with Surki concrete	C.ft.		407	
5	Burnt brick in Surki mortar ...	„		762	
6	Burnt brick slabs of 6" thick ...	S.ft.		508	
7	Plastering ...	Sq.		12·72	
8	New stone work ...	C.ft.		93	
9	Resetting available old stones ..	„		79	
	Total [illegible]	.	...	...	...
	IV. Constructing [illegible] dam across the feeder bella.	L. S.	...	...	...
	Total ...	.	...	...	.
	Contingencies ...	.	..	..	..
	Grand Total ..	..	...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Dated 25th August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. on 2nd September 1930, for opening a new road from Chikanayakanhalli to Settikere, [illegible] Taluk, Tumkur District. An approximate estimate of quantities is given below but the quantities are not guaranteed. The work should be completed before [illegible].

2. The plans, detailed estimates and specifications may be seen at the Executive Engineer's Office, at Tumkur between the hours of 11 A.M. and 3 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. All tenders must be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 100 (four hundred) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for opening a new road from Chikanayakanhalli to Settikere, Chikanayakanhalli Taluk, Tumkur District," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore Circle, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.